TUMKUR DIVISION.

ADVERTISEMENT.

The 7th August 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 30th August 1887 for restoring the Gundagalla Tank, Registered No. 18, Pavagada Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Gundlahalli Tank." In default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Bill of Quantities for restoring the Gundlahalli Tank, Pavagada Taluk.

Items of Work.	Per.	Quantity.	Rate.	Cost.	Total.
Bund.					
Earthwork including watering and tamping..	C. Yd.	11,771			
Burnt new stone work	Do	1,212			
Old stone work	Do	1,978			
Grade stones	No.	23			
Bench mark stones	Do	2			
	L. S. Rs.	50			
Sluice.					
Kodi—Excavation	C. Yd.	125			
Brick in chunam	C. Ft.	3,998			
Concrete	Do	208			
Plastering	Sqr.	16·16			
Covering slabs	S. Ft.	829			
Burnt stone in chunam	C. Ft.	2,205			
Earthwork	C. Yd.	1,792			
New stone work	Do	290			
Old stone	Do	15			

C. T. DALAL,
Executive Engineer.